



Can an 18-Story Building Rise to 24 on Its Existing Foundation?

Load test of existing foundation consisting of driven precast concrete piles

Anna Lenart, DMT Poland
Rune Tranborg Tuxen, DMT Denmark




Short intro of DMT

We are a group of over **50 specialists** focused on pile testing and construction monitoring. As engineers, we like to find solutions where others see problems, providing solutions perfectly tailored to every task.

Solving construction puzzles is our passion!!



The story



The Scene

Denmark, the city of Aarhus.
An 18-story high glass façade building from 2002.
The building is founded on driven precast piles.





The known knows

- Geotechnical information - indicating fissured clay of high plasticity
 - Layout of the foundation and pile plan
 - Driving records for the installed precast piles
 - Cross section 300 mm x 300 mm
 - Embedded length approximately 12 m
- Capacity of foundation from installation
- New "demand" for capacity



The known unknowns

Potential for growth in bearing capacity in +20 years


Up-to-date bearing capacity of the existing foundation piles

The Objective

Verify the bearing capacity of existing foundation piles.

Normally, we would make a static load test with steel beams and reaction piles.

But the conditions this time were different!





What to do? How to do it?

- The scope – Static Load Test
- 4 load tests - 2 outside, 2 inside
 - Use existing building as reaction system





How to do it?



How to do it?




How to do it?




The load test

Load test in 9 steps
Preload and 8 load steps, each of 60 minutes duration
Unloading in 4 steps
Pile head movement surveyed in horizontal and vertical direction






The load test




The load test

Surveying building movement



Achievements - Engineering Takeaways



- The takeaways...
- Failure was reached before planned maximum force
 - Test result indicate the bearing capacity was reached 4-8 weeks after installation
 - Standard Geotechnical calculation does not apply to actual site conditions
 - Additional bearing capacity is needed
 - Monitoring of building show no movement during the Static Load Test
 - Pile test is NEEDED to verify capacities and confirm calculation models and site/soil behavior
 - Data from the past into the future?



The story continues...

- But only the planning is yet in place...





Thank you for your attention!

