

Interpretation of Pile Load Tests


DFI & KIVI Pile Load Testing Seminar

21st October 2021

InPAD

Investigation of the Axial Capacity of Piles in Sand

- **Aim:** Refinement of the Dutch pile design method & improving the understanding of pile behaviour
- October 2019 – October 2023
- Field testing, numerical modelling, laboratory testing
- Project partners:
 - Deltares
 - Fugro
 - Gemeente Rotterdam
 - NVAF
 - Port of Rotterdam
 - Rijkswaterstaat
 - TU Delft



NEN 9997-1

$$q_b = \alpha_p q_{c,avg}$$

$$q_s = \alpha_s q_c$$

- 2016 update: 30% reduction in α_p
- Limiting resistances
 - Base resistance: 15 MPa
 - Shaft resistance: 12-15 MPa
- Koppejan 4D/8D averaging method
- Appropriateness of constant α_s for displacement piles?
- Pile aging




Table 1: Reduction factors for selected pile types from NEN 9997-1

Pile type	α_p	α_s
Bored pile	0.35	0.006
Continuous flight auger	0.56	0.006
Driven cast-in-situ	0.70	0.014
Driven precast	0.70	0.010
Screw injection	0.63	0.009
Steel tubular (open-end)	0.7	0.006

NPR 7201

- Guidance for pile testing: NPR 7201:2017
- Required for reassessing national pile class factors:
 - Static load test until pile failure
 - Minimum 3 piles at two different test sites
 - Pile minimum $8D_{eq}$ ($>3m$) in founding layer
 - Fully instrumented piles
- Also prescribes site investigation, load test procedure, instrumentation etc.

	Driven precast	Screw injection	Vibro
Site 1	✓	✓	✓
Site 2	✓	2021/22	

Test Sites

- **October 2019 – January 2020: Maasvlakte**
 - 4 screw injection
 - \varnothing 610/850 mm; L \approx 37 m)
 - 4 vibro
 - (\varnothing 380/480 mm; L \approx 32m)
 - 3 driven precast
 - (\varnothing 400 mm; L \approx 21m)
- **November 2020 – January 2021: Delft**
 - 3 driven precast
 - (\varnothing 350 mm; L \approx 27 m)
- All piles fully instrumented with fibre optics (Brillouin, FBG)




Maasvlakte




Delft

Maasvlakte



Delft




Test Procedure


- Loaded incrementally until $0.1D_{eq}$ reached
 - Min. eight load steps
- No unload/reload cycles after every load step
 - Occasional unload/reload cycles to fully mobilise base resistance
- Piles not extracted after installation
- Adjustments to creep criteria

$$k = \frac{s_{0,t} - s_{0,t-15}}{\log_{10} \left(\frac{t}{t-15} \right)}$$

Maasvlakte: P11




Delft: P02




Precast Piles

Pile	Pile length (m)	# days between installation & test
P02	31.74	28
P09	31.29	30
P10	31.80	78





— P02 — P09 — P10


Precast Piles





Residual stress



— P02 — P09 — P10




$$\tau_f = \alpha_s q_c h/D^{-0.5}$$



- BOFDA
- NEN 9997-1 (without limiting)
- - - NEN 9997-1 (with limiting)
- UWA-05 (simplified)
- × FBG



Screw Injection Piles

Pile	Pile length (m)	# days between installation & test
P04	37.02	43
P05	37.06	49
P07	34.98	78
P08	34.06	50






— P04 — P05 — P07 — P08

Screw Injection Piles



— P04 — P05 — P07 — P08


- Behaviour indicative of a soil-replacing pile instead of a soil-displacing pile
- 35-50% sand in outcoming grout => primarily soil replacing in founding sand



— P04 — P05 — P07 — P08

Vibro Piles



Pile	Pile Length (m)	# days between installation & test
P01	32.54	59
P03	32.49	34
P06	32.50	50
P11	32.50	52



— P01 — P03 — P06 — P11



Segregation



- Large scatter in strain readings across Pleistocene sand
- Previously observed in other projects
 - De Gaag (Geerling & Janse, 1997)
 - Prepal Rijswijk (Geerling & Janse 1993)
- Potentially influenced by concrete quality, reinforcement and high stresses in the Pleistocene sand
- Difficult to interpret readings at the pile base





(Geerling and Janse, 1993)

Vibro Piles





(White & Bolton, 2004)





Conclusion

- Field tests have given a clear insight into the individual mechanisms of pile response
 - Mobilisation of SI pile base resistance
 - Friction fatigue in displacement piles
- Clear scope for improving the national standard
- Conservatism of limiting resistances
- Effects of averaging method on derived α_p
- High residual loads developed in the precast piles → significant effect on pile test interpretation and α_p

Future

- Screw injection pile tests at Delft
- SW22: Pilot site
- SI & vibro pile database evaluation
- Reliability/probabilistic-based assessment
- Influence of weak layers & sensing distance
 - Centrifuge testing
 - Instrumented jacked piles (Drukpaal)
- Numerical modelling
 - Modelling the effect of weak layers in FEM & DEM



(Therani et al., 2017)

Questions?

k.duffy@tudelft.nl

Dirk.deLange@Deltares.nl